

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 80-16 Location: Ellis Co. NE NE NW

County: Ellis Sec. 28 Twp. 11 Rge. 18 (E) (W)

Name of Field or Pool: \_\_\_\_\_ Total Depth: 3535

I have this date completed supervision of plugging of:

Well No. 1 Lease Treas

Operator's Full Name Gulf Oil Corp

Complete Address: Gulf Bld Box 661 Tulsa Okla.

Plugging Contractor: Morgan Well Plugging

Address: Hutchinson Kansas License No. \_\_\_\_\_

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 9pm Day 19 Month Feb Year 1958

The above well was plugged as follows:

T. D. 3535 8 5/8" set at 1300, 5 1/2" set at 3528 with 100 sacs cement cir.

~~Chat to 3500' and displaced 4 sax cement with dump bailer, Broke pipe at 2750' and pulled pipe to 600' and circulated hole with heavy mud, displaced 20 sax cement, pulled pipe to 200', heavy mud and displaced 20 sax cement, heavy mud to 40' built rock bridge and topped with ten sax cement to bootom of cellar. Mud and cementing by Halliburton.~~

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: Herbert P. Leiker  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
2-25-1958

Reviewed: J. Lewis Brock  
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

PLUGGING  
FILE SEC 28 T. 11 R. 18  
BOOK PAGE 80 LINE 16