

15-051-20705-00-00

Form CP-3
Rev. 6-4-68

KANSAS

M STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
1-5-1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. Scott Ritchie & Maderia Oil Company

Complete Address 412 Union Center Bldg., Wichita, Kansas

Lease Name Meistrell "A" Well No. 1

Location SE SE SW Sec. 10 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3177

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Hellar Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5:30 P Day 29 Month 12 Year 1970

The above well was plugged as follows:

RTD 3177' 8 5/8 csg set at 257' cwc Gmt. Mat. 50-50 poz 2% gel.

Gunned pits, circulated heavy mud, set cementing plug at 420' and displaced 25 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1-6-71
INV. NO. 3169-W

Signed: *Leo J. Mansing*
Well Plugging Supervisor