


WELL PLUGGING RECORD

All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 23 Twp. 10 Rge. (E) 23 (W)  
Location as "NE/CNW/SW" or footage from lines C SW 1/4  
Lease Owner Herman Geo. Kaiser, Oil Producer  
Lease Name Conness A Well No. 3  
Office Address 909 Palace Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed Sept 1 19 58  
Application for plugging filed Sept 1 19 58  
Application for plugging approved Sept 1 19 58  
Plugging commenced Sept 1 19 58  
Plugging completed Sept 1 19 58  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3880 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	2 1/4	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with Rotary Mud to 600 ft, set  
plug and cemented with 20 sacks cement  
through drill Pipe. Mudded hole to 200 ft, set plug  
and cemented with 20 sacks cement through drill  
pipe. Mudded to 40 ft, set plug and cemented  
with 10 sack cement to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H 30, Inc.  
Address 709 Petroleum Bldg., Wichita Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
L. C. Sponenberg employee of contractor  
(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 5 day of Sept., 19 58

My commission expires Feb. 13, 1960

Rose Turley  
Notary Public.

PLUGGING  
FILE SEC 23 T. 10 R. 23W  
BOOK PAGE 126 LINE 18

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1958  
09-06-1958  
CONSERVATION DIVISION  
Wichita, Kansas

**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser, Oil Producer**

SEC. 23 T. 10 R. 23 W

FARM **Conness A**

NO. 3

**15-065-02304-00-00**


LOC. C SW 1/4

TOTAL DEPTH **3880'**  
 COMM. **8/23/58**

COMP. **9/1/58**

COUNTY **Graham**

SHOT OR TREATED  
 CONTRACTOR **H 30, Inc.**  
 ISSUED



CASING		
20	10	
15	8	214'
12	6	
13	5	

ELEVATION **2354 K.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	75'
Shale & Shells	740'
Shale & Shale with sand Stks	970'
Sand with strace of Pyrite	1160'
Shale & Shells	1355'
Sand & Gravel	1610'
Shale and Red Bed	1755'
Shale and Shells & Red Bed	1885'
Anhydrite	1925'
Shale and Shells	2395'
Shale with Lime stks	2445'
Lime & Shale	2975'
Lime	3090'
Shale ' Lime	3645'
Lime	3694'
Kansas City Lime	3747'
Lime	3775'
Kansas City Lime	3833'
Lime	3880'

Formation Tops:

Topeka	3394'
Heebner	3618'
Toronto	3638'
Lansing Kansas City	3652'
Base Kansas City	3876'

RECEIVED  
 SEP 13 1958  
 COUNTY OF SEDGWICK

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H 30, Inc.

By *[Signature]*

STATE OF KANSAS

SS,

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 5 of September 1958.

*[Signature]*  
 Notary Public

My Commission Expires Feb. 13, 1960

**PLUGGING**  
 FILE SEC. 23 T. 10 R. 23 W  
 BOOK PAGE 126 LINE 18