


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 23 Twp. 10 Rge. 23 (XX) (W)
Location as "NE/CNWxSWx" or footage from lines W/2 W/2 SW
Lease Owner Herman George Kaiser, Oil Producer
Lease Name Conness A Well No. 2
Office Address 4220 East 51st St. Tulsa, Okla. 74135
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed July 1 19 58
Application for plugging filed July 19 19 74
Application for plugging approved July 11 19 74
Plugging commenced October 18 19 74
Plugging completed October 18 19 74
Reason for abandonment of well or producing formation economics

If a producing well is abandoned, date of last production July 2 19 74
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well William Nickols
Producing formation Lansing Kansas City Depth to top 3631 Bottom 3852 Total Depth of Well 3878 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Topeka</u>	<u>Lime</u>	<u>3374</u>	<u>3395</u>	<u>8 5/8" OD</u>	<u>201'</u>	<u>none</u>
<u>Lans/ KC</u>	<u>Lime</u>	<u>3631</u>	<u>3852</u>	<u>5 1/2" OD</u>	<u>3876'</u>	<u>2972'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand plug from 3650' to 3625'
Cement plug from 3625' to 3593'
Gel and cement plug from 1000' to 675'
Gel plug from 675' to 235'
Cement plug from 235' to 160'
Gel plug from 160' to 140'
Cement plug from 140' to surface

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1974
CONSERVATION DIVISION
Wichita, Kansas
10-21-1974

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

I, Robert R. Scott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert R. Scott
P.O. Box 791 Hays, Ks 67601
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 74

My commission expires November 13, 1976

Carol J. Huff
Notary Public.

15-065-01884-00-00


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAFETY BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Francis Oil & Gas, Inc.
FARM Conness A NO. 2

SEC. 23 T. 10 R. 23
LOC. CW 1/2 W 1/2 SW 1/4

TOTAL DEPTH 3878
COMM. 6/10/58 COMP. 6/22/58
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COUNTY Graham



CASING		
20	10	
15	8	201'
12	6	
13	5	3876'

ELEVATION 2344 K.B.
2341 D.F.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface soil	40'
Clay & sand streaks	110'
Shale	201'
Shale & Shells	375'
Blue Shale	625'
Shale - Shells with clay & sand stks	995'
Gravel - sand w/ heavy stks Iron Pyr	1110'
Shale	1270'
Sand	1275'
Red Bed with Sand stks	1440'
Sand	1610'
Shale & shells - Red Bed	1880'
Anhydrite	1922'
Shale & Shells	2385'
Shale with Lime stks	2490'
Shale & Lime	3640'
Lime	3674'
Kansas City Lime	3715'
Lime	3727'
Kansas City Lime	3838'
Lime	3839'
Kansas City Lime	3880'
T. D. Corrected 2 ft.	3878'

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1 1974
CONSERVATION DIVISION
Wichita, Kansas
07-11-1974

Formation Tops:

Topeka	3374'
Heebner	3595'
Toronto	3617'
Lansing K. C.	3631'
Base K. C.	3852'
T. D.	3878

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H 30, Inc.
By C. P. Spruery

STATE OF KANSAS
SS,
COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 27 of June 1958.

Rose Furey
Notary Public

My Commission Expires February 13, 1960