


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Graham County. Sec. 25 Twp. 10 Rge. 23 (E) W (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE NE

Lease Owner Cooperative Refinery Association

Lease Name Griffith Well No. 1

Office Address Box 765 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed November 29 19 51

Application for plugging filed December 3 19 51

Application for plugging approved December 4 19 51

Plugging commenced November 29 19 51

Plugging completed November 29 19 51

Reason for abandonment of well or producing formation

dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4180 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-Kansas City	water	3876	3903	8 5/8"	200	
Arbuckle	water	4150				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud bottom to 190'  
Bottom plug set at 190'  
Cemented with 150 sacks cement  
Filled with heavy drilling mud 190' to 40'  
Top plug set at 40'  
Cemented with 10 sacks to top

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Cooperative Refinery Association

Address Box 765 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

L. M. Collins

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. M. Collins

Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day of December, 19 51

Arthur J. Johnson  
Notary Public

My commission expires February 14, 1955

23-5091-s 8-50-10M

DEC - 6 1951

CONSERVATION DIVISION  
Wichita, Kansas

12-6-1951

15-065-00270-00-00

Griffith #1

NE NE NE 25-10S-23W

OWNER: Cooperative Refinery Association

Graham County, Kansas

Contractor: Cooperative Refinery Association

Casing: 200' of 8 5/8"

Comm: 11-13-51 Comp: 11-29-51

Elevation: 2360 D.F.

	<u>From</u>	<u>To</u>	<u>Geological Tops</u>	
Rock, Sand & Shale	0	200	Topska	3388
Shale & Shells	200	220	Heebner	3610
Surface Clay, Sand & Shells	220	830	Base-Kans City	3876
Sand & Shells	830	885	Marmaton	3903
Shale, Shells & Sand	885	1225	Penn. Basal Cong	4045
Sand & Shale	1225	1660	Simpson	4145
Shale & Shells	1660	1900	Arbuckle	4150
Anhydrite	1900	1920		
Shale & Shells	1920	2385		
Lime	2385	2745		
Lime & Shale	2745	3680		
Lime	3680	4090		
Lime & Pyrite	4090	4125		
Lime	4125	4180		
Total Depth	4180			

STATE OF KANSAS )

COUNTY OF BARTON )


I hereby certify that the above is a true and correct copy of the log on the Griffith #1 well located NE NE NE 25-10S-23W, Graham County, Kansas.

L. M. Collins

Subscribed and sworn to before me this 3rd day of December, 1951.

Arthur J. Robinson

My Commission Expires: February 14, 1955



**PLUGGING**  
FILE SEC 25 T 10 R 23 W  
BOOK PAGE 128 LINE 7

RECEIVED  
STATE CORPORATION COMMISSION  
DEC - 6 1951  
CONSERVATION DIVISION  
Wichita, Kansas  
12-06-1951