

Side TWO

OPERATOR Foxfire Exploration, Inc. LEASE NAME Lynd SEC 18 TWP 11 RGE22 (W)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<p>Check if no Drill Stem Tests Run. <input checked="" type="checkbox"/> Check if samples sent Geological Survey.</p> <p>Sand and Shale Shale Lime and Shale Shale and Lime</p> <p>DST #1 - 3854-3883. 60-60-60-60. Rec. 1673.53' oil, 225.65' gas. IFP 173-434#. FFP 521-650#. ISIP 963#. FSIP 952#</p> <p>If additional space is needed use Page 2</p>	0 2318 3100 3883	2318 3100 3883 3940	Anhydrite Anhy. Base Topeka Heebner Toronto Lansing BKC Marmaton Marm. PZ Arbuckle LTD RTD	1709 1756 3303 3517 3540 3554 3781 3856 3862 3934 3944 3940

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)							
Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	292'	60/40 Poz	200	2% gel, 3% cc
Production	7 7/8"	5 1/2"	15.5#	3938'	Common	115	2% gel
					Common D-29	100	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	.42" Jet	3864-3880

TUBING RECORD	
Size	Setting depth
2 7/8"	3834'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
600 gal. mud acid., 15% INS. 10% Polysolv, 116,000 gal.	3864-3880
gelled water frac with 200 sx 20/40/ and 600 sx 10/20 sand	

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
9/18/83		

Estimated Production-I.P.	Oil	Gas	Water	Gas-oil ratio	CFPB
	70 bbls.	MCF	85 % 400 bbls.		

Disposition of gas (vented, used on lease or sold)	Perforations
vented	3864-3880