

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-031-22395-00-00  
Spot: SWSWNENW Sec/Twnshp/Rge: 34-22S-16E  
1100 feet from N Section Line, 1540 feet from W Section Line  
Lease Name: WHITELEY Well #: 15  
County: COFFEY Total Vertical Depth: 1090 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	34 SX

35.43

Well Type: Oil DH KCCPKT UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/02/2009 8:00 AM  
Plug Co. License No.: 31440 3396 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: DENNIS KERSHNER Company: COLT ENERGY, INC Phone: (620) 365-3111

Proposed Plugging Method: THIS WELL CONSISTED OF AN UN CASED BORE TO 857'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 625', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 01/20/2009 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN INTO THE WELL TO T.D.. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO T.D..THE DRILL PIPE WAS PULLED TO 625' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
KCC DISTRICT #3

FEB 25 2009 CPT

CHANUTE, KS

INVOICED  
DATE 3-12-09  
INV. NO. 3009061317

RECEIVED  
MAR 02 2009  
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PKT