

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25811-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 31-13S-16W  
2240 feet from N Section Line, 520 feet from E Section Line  
Lease Name: S.FARM EAST LEASE Well #: 1  
County: ELLIS Total Vertical Depth: 3589 feet

Operator License No.: 33386  
Op Name: C G OIL, LLC  
Address: 2550 AIRBASE RD PO BOX 207  
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3586	0	200 SX
SURF	8.625	1097	0	450 SX

116.04

Well Type: LDH KCC PFA DEL CP2/3  
UIC Docket No:

Date/Time to Plug: 02/26/2009 9:00 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: FRANK Company: C G OIL, LLC Phone: (785) 735-2274

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Cut 5 1/2" at 1158'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/26/2009 5:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3560' - pumped 50 sxs cement.  
Pulled tubing out - cut casing at 2050' - 1800' - 1550' - 1158' - cut and got loose at 1158'.  
Tied onto 5 1/2" - pumped 400 sxs cement - on vacuum - stopped pulling casing.  
Pumped 75 sxs cement down - top filled hole - done.  
  
Note: Operator opted to run tubing to bottom and pump 50 sxs cement in lieu of sanding off to 50' above perf and dumping 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3492	3495		
3399	3402		
3302	3306		
3291	3294		
3246	3251		
3217	3224		

INVOICED  
DATE 3-12-09  
INV. NO. 2009061315

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 03 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #37478.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

FEB 27 2009