

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24074-00-00
Spot: NESWNE Sec/Twnshp/Rge: 26-18S-21W
1690 feet from N Section Line, 1600 feet from E Section Line
Lease Name: WELLS Well #: 1-26
County: NESS Total Vertical Depth: 4190 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		
PC		2282		WITH 270 SX CMT
PROD 5.5		4187	0	WITH 370 SX CMT
SURF 8.625		227		WITH 150 SX CMT

Well Type: Oil Gas KCC District open UIC Docket No: _____ Date/Time to Plug: 03/03/2009 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PUMP 300# HULLS WITH BOTTOM CMT AND FILL WITH CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2009 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 300# HULLS & 225 SX CMT. MAXIMUM PRESSURE 750#. SHUT IN PRESSURE 500#. TIED ONTO BACKSIDE & PRESSURED UP TO 500# IMMEDIATELY. NO CMT DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
2234	2240		
2195	2199		

INVOICED
DATE 3-20-09
INV. NO. 2009061341

RECEIVED
MAR 12 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
MAR - 6 2009

Signed Michael Maier
(TECHNICIAN)

KCC DODGE CITY

Form CP-28
AG