

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23194-00-01  
Spot: SENENE Sec/Twnshp/Rge: 30-17S-21W  
4672 feet from S Section Line, 701 feet from E Section Line  
Lease Name: BRENNER Well #: 1  
County: NESS Total Vertical Depth: 1224 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: PO BOX 544 N HWY 283  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1224	0	WITH 250 SX CMT TO SURFACE
SURF	8.625	280		WITH 160 SX CMT

Well Type: SWD UIC Docket No: D25315.0 Date/Time to Plug: 03/04/2009 11:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3614

Proposed Plugging Method: RUN TBG TO TOP OF PERFS AND CIRCULATE CMT & HULLS. PULL TBG & TOP OFF. TIE ONTO BACKSIDE AND PUMP 50 SX CMT IF POSSIBLE.

39.78

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/04/2009 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN TBG TO 930'. PUMPED 300# HULLS & 100 SX CMT. DID NOT CIRCULATE CMT. PULLED TBG TO 500' & PUMPED 25 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. DUG BACKSIDE OUT. IT WAS FULL OF CMT.

Perfs:

INVOICED  
DATE 3-20-09  
INV. NO. 2009061345

RECEIVED  
MAR 12 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES

Plugged through: TBG

District: 01

RECEIVED  
MAR - 6 2009  
KCC DODGE CITY

Signed Michael Maier  
(TECHNICIAN)