

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24869-00-00
Spot: SENESE Sec/Twnshp/Rge: 28-20S-21W
1819 feet from S Section Line, 524 feet from E Section Line
Lease Name: BIEBER Well #: 2
County: NESS Total Vertical Depth: 4470 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4462	2240	WITH 175 SX CMT
SURF	8.625	222		

145.28

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/04/2009 1:30 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICE, INC. Phone: (785) 398-2289

Proposed Plugging Method: SAND 50' ABOVE PERFS & 5 SX CMT OR CIBP & 2 SX CMT. LOAD HOLE WITH MUD & 50 SX CMT AT 1480'. PLUG AT 620' WITH 60 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2009 6:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG SAND TO 4330' & 4 SX CMT. 2ND PLUG AT 1480' WITH 50 SX CMT. 3RD PLUG AT 620' WITH 60 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4414	4417		

INVOICED

DATE 3-20-09
INV. NO. 2009061346

RECEIVED
MAR 12 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
MAR - 6 2009
KCC DODGE CITY

Form CP-273

PKT