

15-195-21434-00-00
8-9

6 070788

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW NE NE, SEC. 22, T 11 S, R 22 W/EXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Operator: Lebsack Oil Prod
Name & Address: Box 489
Hays, Ks. 67601
Rex Curtis

feet from S section line
feet from E section line

Lease Name Zeman Well # 1-22

County Trego 131.63

Well Total Depth 4050 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement Co. Hembree License Number

Address Hays, Kansas Ellis Ks.

Company to plug at: Hour: AM Day: 9 Month: August Year: 19

Plugging proposal received from Rex Curtis

(company name) Lebsack Oil Prod (phone)

were: 8 5/8" 256' cwc w/150 sks cement. 4 1/2" casing 4049' w/150 sks cement.

STATE CORPORATION COMMISSION
RECEIVED
AUG 17 1989
8-17-1989
CONSERVATION DIVISION
WICHITA, KANSAS

PBTD 3970'. Perfs 3896 - 3755. Hole in Dakota at approx 950'. F.O. tool at

1786' - 89'. Proposal 300 sks 65/35 poz 8% gel and 5 sks hulls.

Run tubing to a minimum of 3900' and spot cement. Load both 4 1/2" casing and 4 1/2" casing and 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:30PM Day: 9th Month: August Year: 1989

ACTUAL PLUGGING REPORT Ordered 300 sks 65/35 poz 8% gel and 5 sks hulls. Pumped in

with pump truck. Spotted through tubing. 1. 2 3/8" tubing at 3904'. Spotted 90

sks cement w/2 sks Hulls. 2. Opened F.O. tool at 1786'. 3. 2 3/8" at 1786' w/ 60 sks cement. 4. 2 3/8" at 1694' w/90 sks cement. [Cement circulated] w/2 sks hulls.

5. Squeezed 4 1/2" casing w/6 sks cement. Max pressure 400 psig. Shut in at 400 psig.

6. Pumped 130 sks in 4 1/2" and 8 5/8" annulus. Max pressure 300 psig. Shut in at 250

Remarks: psig. Cemented by Halliburton Cement. Hays. (Returned for ad additional 75 sks cmt. (If additional description is necessary, use BACK of this form.) Total cement 375 sks w/4 sks hulls.

INVOICED
I will not observe this plugging.

DATE 8-21-89

INV. NO. 25698

Gib S.

Signed Marion J. Schmidt (TECHNICIAN)