

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20956-00-00  
Spot: CNWNWNW Sec/Twnshp/Rge: 22-11S-22W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: FLAX Well Number: 1  
County: TREGO Total Vertical Depth: 3950 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 258  
Production: Size 4.5 feet: 3950  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/21/2002 9:00 AM

Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC

Proposal Rcvd. from: LEON PFEIFER Company: PFEIFER DOZER SERVICE, LLC Phone: (785) 627-5711

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 275 sxs 60/40 pozmix with 500# hulls.  
Plug thru tubing.  
Perfs at 625' - 1650' - 2150'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/21/2002 2:15 PM

KCC Agent: ROGER MOSES

**Actual Plugging Report:**

8 5/8" S.P. at 258' w/165 sxs cement. 4 1/2" casing at 3950' w/250 sxs cement.  
Ran tubing to 2200' - spotted 100 sxs cement and 400# hulls. Cement circulated.  
Pulled all tubing - pumped 50 sxs cement and 100# hulls into 4 1/2" casing to Max. P.S.I. 1000#. S.I.P. 400#.  
Tied to 8 5/8" x 4 1/2" annulus and pumped 25 sxs to Max. P.S.I. 400#. S.I.P. 0#.  
Total of 175 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED  
FEB 26 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. PFEIFER WELL SERVICE-WATER.

Plugged through: TBG

District: 04

Signed

Roger L Moses

(TECHNICIAN)

107

Form CP-2/3

FEB 26 2002

replacement card

TRIPLE H OIL OPER  
HAYSKS

22-11S-22W  
NW NW NW

# 1 FLAX

site: 6-1/2 N & 1 W OF OGALLAH KS	city: TREGO	API 15-195-20956	<table border="1"> <tr><td>•</td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> </table>	•											
•															
contr: DREILING OIL	field: GAGELMAN EXT (1/8 S)														
gd:															
fr date 02/24/82	spc date 02/17/82	drig comp 02/25/82	card issued 10/13/83	last revised 05/10/99											

ELV: 2203 KB, 2198 GL DRLRS  
 tops.....depth/datum  
 ANH.....1660 + 543  
 B/ANH.....1695 + 508  
 ARB.....3935 -1732  
 RTD.....3950 -1747

IP status  
 OIL, ARB, INTV NA , (NEW PAY) , 10/06/83  
 INFO RELEASED: 5/10/99 - WAS OIL WELL - TIGHT HOLE  
 CSG: 8-5/8" 258 / 165 SX, 4-1/2" 3950 / 250 SX  
 DRLR SD ZNS: 1047-1165 (SH & SD STRKS), 1165-1407  
 NO CORES OR DSTS RPTD  
 TRGT ZN: ARB (OIL), PTD 3950 (ARB), MICT - CO, PF (ARB) INTV NA, SWB DWN, SO, POP, OIL WELL (POTENTIAL NOT PTD), 10/6/83 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS; ALL REQUESTS FOR INFO DENIED

COPYRIGHT 1999  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS