

10-5 15-195-21999-00-00

6 050019

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-21,999-00-00

C SE SW, SEC. 22, T 11 S, R 22 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7875

Lease Name Schubert Well # 4

Operator: Strata Energy Resources
Name & Address: 4101 Birch Street Suite 130
Newport Beach, Ca 92660

County Trego 127.92
Well Total Depth 3936 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083

Address Hays, Ks.

Company to plug at: Hour: _____ AM Day: 5 Month: Oct Year: 19 88

Plugging proposal received from Greg Micalson

(company name) Western Kansas Drilling (phone) _____

were: Order 205 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with

Good circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
12-16-1988
DEC 16 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:30AM Day: 5 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT
1st plug at 1800' w/25 sks Anhydrite
2nd plug at 935' w/100 sks 1 sk F.C. Dakota
3rd plug at 320' w/40 sks
4th plug at 40' w/10 sks
15 sks in rathole 15 sks in mousehole

Remarks: Allied Russell
(If additional description is necessary, use BACK of this form.)

Inspector did not observe this plugging.

Signed Bruce D. Basye (TECHNICIAN) [Signature]

INVOICED

DATE DEC 19 1988

INV. NO. 23411

JAN 06 1989