

6-070945

15-195-20999-00-00

180
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-20,999-00-00

1650
ES 2/25/09
KCC

SW NW SW /4 SEC. 27, 11 S, 22 W
1980 feet from S section line
4950 feet from E section line

Operator license# 8572 Lease Rohr well # 1

Operator: Reach Oil Corp. County Trego

Address: d/b/a Reach Group Well total depth 4065 feet
229 E. William #500 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 257 feet

132.11

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License#

Address: 1707 East 10th Street, Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 4th Month: September Year: 91

Plugging proposal received from: Earl Ringeisen

Company: Reach Group phone: 316-262-1522

Were: 8 5/8" 257' S.P. cvc. w/175# cement. 4 1/2" casing set at
4048' w/1000 sx. Completed top stage when casing was set. 4 1/2" casing
cvc. Perf. 3948' - 3608'. Proposal 275 sx. 65/35 pozmix - 8% gel. and
5 sx. hulls. Load both 4 1/2" casing and 4 1/2" x 8 5/8" annulus with
cement and shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30PM, Day: 4th, Month: September, Year: 91

Actual plugging report: Reach Group ordered 275 sx. 65/35 pozmix -
8% gel. - and 5 sx. hulls. Pumped in 4 1/2" casing w/15 sx. cement
followed w/200 sx. w/5 sx. hulls added. Max. pressure 700 P.S.I.
Shut in @ 675 P.S.I. Pressured annulus 4 1/2" x 8 5/8" to 450 P.S.I.
Max. pressure shut in at 450 P.S.I. Did not take cement.

RECEIVED
STATE CORPORATION COMMISSION
10-1-1991
OCT 01 1991

Remarks: Cemented by B.J. Services, Hays, Kansas 67601
CONSERVATION DIVISION
Wichita, Kansas

I did / did not observe the plugging.

Marion J. Schmidt

DATE 10-28-91

INV. NO. 33894

Feb. S.

(agent)

Form CP-2/3

9-4