

6 020180

15-195-21614-00-00

API NUMBER 15-195-21,614-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW, SEC. 27, T 11 S, R 22 W/4

990 feet from ^{SE}~~NYS~~ section line

3630 feet from ^{SE}~~WYE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Rohr Well # 2

Operator: The Reach Group

County Trego

Name & Address 3751 E. Douglas

Well Total Depth 1950 63.38 feet

Wichita, Ks. 67218

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Robert Gay, Energy Drilling License Number 6033

Address Hutchinson, Ks.

Company to plug at: Hour: AM Day: 6 Month: November Year: 19 84

Plugging proposal received from Bud Benoit

(company name) woberth Gay, Energy Drilling (phone) _____

were: Order 195 lbs. 50/50 pozmix 6% gel 3% cal. cl. , 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 3 PM Day: 6 Month: November Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 1830 w/25 sks
- 2nd plug @ 960 w/100 sks
- 3rd plug @ 300 w/40 sks
- 4th plug @ 40 w/10 sks
- 10 sks in Rat Hole and 10 sks in Mouse Hole

RECEIVED
STATE CORPORATION COMMISSION
11-13-1984
NOV 13 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 11-19-84

DEC 07 1984

Signed *Justin Ballthagen* 9-84
(TECHNICIAN)

INV. NO. 4806

11-6