

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00213-00-01
Spot: SESESE Sec/Twnshp/Rge: 30-11S-22W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: EHR FARMS INC Well Number: 1
County: TREGO Total Vertical Depth: 4120 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size _____ feet: 8/33.90
Surface Casing: Size 8.625 feet: 190
Production: Size 4.5 feet: 4020 w/150 sxs cmt
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2002 8:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered out 220 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/04/2002 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1820' and 1250'.
Hooked onto 8 5/8" - pumped to pressure with 25 sxs.
Max. P.S.I. 300#. S.I.P. 100#.
Swaged onto 5 1/2" - mixed and pumped 25 sxs with 300# hulls followed by 14 sxs gel.
Topped with 150 sxs cement with 200# hulls.
Max. P.S.I. 700#. S.I.P. 500#.

RECEIVED
KANSAS CORPORATION COMMISSION
4-9-2002
APR - 9 2002
CONSERVATION DIVISION

Remarks: LEASE ORIGINALLY KNOWN AS BAKER #1. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 4-10-02

INV. NO. 2002061634

Form CP-2/3

APR 08 2002

CLA-MAR OIL COMPANY

"OWWO"

30-11-22W

2705 VINE STREET, #8

#1 E.H.R. FARMS, INC.

SE SE SE


HAYS, KS 67601

CONTR HELBERG DRILLING

CTY TREGO

GEOL

FIELD BIN



ELV 2384 KB SPD 11/25/82 ^{CARD}ISSUED 3/17/83 IP P 30 BOPD, TR WTR
MARM 3984-4004

API NOT ASSIGNED

SMP	Tops	Depth: Datum
ANH	1795+	589
TOP	3415-	1031
HEEB	3607-	1223
LANS	3637-	1253
CONG	4021-	1637
ARB	4070-	1686
TD	4120-	1736

OLD INFO: OPERATOR WAS DAVIS BROTHERS, #1 BAKER, SPD
NA, SET 8" 190, COMP AS D&A 7/20/51, CONTR: UNKNOWN
NO DST'S

NEW INFO: RE-ENTERED 11/25/82, WSH DWN, SET 4 1/2 "
4120/150SX, , MICT - CO, PF (MARM) 3984-4004. AC 1000G
(10%), FRAC 30,000# SD & 30,000G GEL W, POP, P 30 BOPD,
TR WTR, 1/19/83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS