

12-8 15-195-21474-00-00

To: 6 070731
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-21,474-00-00
SW , SEC. 30, T 11 S, R 22 W/E
330 feet from S section line
860 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration Inc.
Name & Address 125 N. Market #1000
Wichita, Ks. 67202

Lease Name Rhoades Well # 1
County Trego 132.60
Well Total Depth 4080 feet
Conductor Pipe: Size 0 feet
Surface Pipe Size 8 5/8 feet 206

Abandoned Oil Well Gas Well Input SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co.

Address Box 31, Russell, Ks. 67665

Company to plug at: Hour: PM Day: 8 Month: Dec Year: 19 88

Plugging proposal received from Tom Post

(company name) Ritchie Exploration Inc. (phone)

were: 8 5/8" 206' S.P. cwc w/150 sks cement. 4 1/2" casing set at 3877' w/125 sks cement.

Port collar at 1822' cwc w/500 sks cement. PBTB 3855'. No casing recovery. Perfs at
3710' - 13', 3639' - 42', Proposal 250 sks 65/35 Poz 6% Gel and 5 sks Hulls. Pump in with
pump truck, load pressure both 4 1/2" and 8 5/8" annulus and 4 1/2" casing with cement. Shut in
under pressure.

Plugging Proposal Received MSJ Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 8 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT Ordered 250 sks 65/35 Poz 6% Gel and 5 sks Hulls.

Pumped in with pump truck. 1. Pressured 4 1/2" casing and 8 5/8" annulus with cement. Max
pressure 500 psig. Shut in at 500 psig. (annulus D.V.) Did not take cement.

2. In 4 1/2" casing pumped in 25 sks cement followed with another 215 sks cement w/5 sks Hulls
added in. Max pressure 1000 Psig. Shut in at 500 psig.

Remarks: Cemented by Allied Cement
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 1-11-89

INV. NO. 23615 FEB 10 1989

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt