

6030457

15-195-21727-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21-727-00-00

N/2 NENW SEC. 30, T. 11 S, R. 22 (W) E

4950 feet from M(S) section line

3300 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name RICHARDSON Well # C-4

Operator: A. SCOTT RITCHIE

County TREGO 128.22

Name & Address 125 N. MARKET, Ste. 950

Well Total Depth 3945 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor MURFIN DRUG CO. License Number 6033

Address WICHITA, KANSAS

Company to plug at: Hour: AM Day: 29 Month: 5 Year: 19 85

Plugging proposal received from SCHIEFERECKE

(company name) MURFIN DRUG (phone) _____

were: 8 5/8 SET @ 218 W/165 SX. WITH HOLE CIRC. W/ NO LESS THAN 36 VIS.

MUD. AND NO LOSS OR GAIN OF FLUID, SPOT CEMENT PLUGS WITH DRILL

PIPE. ORDER 190 SX. 50/30 PZ 6 PAGES 3 HOLE, 1 SX. CELLO FLAKE, 8 5/8 W.P.

ALLIED CEM. Co., WATER FROM IRRIGATION WELL,

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:AM Day: 29 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 1775', DISPLACE 25 SX. CEM. MIX. LAYDOWN

D.P. TO 825' DISPLACE 100 SX. CEM. MIX. + 1 SX. CELLO FLAKE. LAYDOWN D.P.

TO 300' DISPLACE 40 SX. CEM. MIX. LAYDOWN D.P., PUSH 8 5/8 W.P. TO KELLY

DEPTH. FILL HOLE FROM W.P. TO BASE OF CELLAR. WITH 10 SX. CEM. MIX.

DISPLACE 15 SX. CEM. MIX. IN RATHOLE W/A JOINT OF PIPE. PLUG COMPLETE

RECEIVED
STATE CORPORATION COMMISSION
6-7-1985

Remarks: ELEV. 2304 ANHY 1765-1817 NOARB. NO LOSS OF FLUID NOT NEAR PROD.
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed Carl Goodnow
(TECHNICIAN)

DATE 6-12-85

INV. NO. 8474

19
6-6-85
mmj