

2-28 15-195-20849-00-00

6 061788

API NUMBER 15- 195-20,849-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SE , SEC. 32 , T 11 S, R 22 W/Ex
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Hixson Well # 1
Colins

Operator: Richie Exploration

County Trego 132.44

Name & Address 125 N. Market

Well Total Depth 4075 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 3:00PM Day: 28 Month: Feb Year: 19 89

Plugging proposal received from Vern Duntz

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 250 sks 60/40 Poz 8% Gel 5 sks Hulls

RECEIVED
STATE CORPORATION COMMISSION
3-21-1989
MAR 21 1989

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45PM Day: 28 Month: Feb Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 209' w/190 sks. 4 1/2" set at 4075'

w/125 sks. Top perf at 3726'. Plugged bottom w/sand and 4 sks cement to 1400'. Shot pipe open time and recovered 1300'. Pumped in 8 5/8" 25sks cement followed w/5 sks Hulls in 225 sks cement w/900 psi.

Remarks: By Allied Ran line to 1200'
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN)

DATE 3-22-89
INV. NO. 24194

Gilbert G. Scheck