

15-195-20637-00-01

7-10

4-110020

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-20,637-00-01

SW SW SW _____ /4 SEC. 32, 11 S, 22 W
330 _____ feet from S section line
4950 _____ feet from E section line

Operator license# 4767

Lease: Spena Well # C-2

Operator: Ritchie Exploration, Inc.

County: Trego 134.68

Address: 125 N. Market - Suite #1000
Wichita, Kansas 67202

Well total depth 4144 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 247 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Mike's Salvage & Testing License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 8:30A.M. Day: 10 Month: July Year: 1997

Plugging proposal received from: Mike Kelso

Company: Mike's Salvage & Testing Phone: 316-938-2537

Were: Order 240 sxs 60/40 pozmix - 10% gel and 500# hulls. Run 105 sxs and 300# hulls at 2315'. Pull casing to 1910' and pump 35 sxs 60/40 pozmix - 10% w/100# hulls. Pull to 1050' and run 35 sxs 60/40 pozmix - 10% gel w/100# hulls. Pull to 225' and circulate with 45 sxs 60/40 pozmix - 10% gel. Pull remainder casing and top off with 25 sxs.

7-18-1997
11:20
RECEIVED
DOWN

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 10, Month: July, Year: 1997

Actual plugging report: Shot 4 1/2" casing at 2315', could not pull. Shot 4 1/2" at 1910' and it still would not pull. Pumped 80 sxs 60/40 pozmix - 10% gel w/300# hulls at P.S.I. 500# down 4 1/2" casing. Pumped 17 bbls water behind these 80 sxs. Shot 4 1/2" casing at 900', still could not pull casing. Shot 4 1/2" casing at 790' and pulled 80' (2 joints) and pumped 50 sxs 60/40 pozmix - 10% gel w/200# hulls at P.S.I. 500#. Pumped 4 bbls water after 50 sxs. Pulled 560' of 4 1/2" and circulated 40 sxs 60/40 pozmix - 10% gel to top. Pulled remainder casing. Topped off with 10 sxs 60/40 pozmix - 10% gel. Total 180 sxs cement and 500# hulls.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES _____, CALC X, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 2422 GL

I did [X] / did not [] observe the plugging.

Roger Moses
(agent)

Form CP-2/3

INVOICED

DATE JUL 21 1997

INV. NO. 48607

7-10