

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24079-00-00

Spot: SWSNW

Sec/Twnshp/Rge: 23-18S-21W

2814 feet from W Section Line, 1800 feet from W Section Line

Lease Name: WELLS

3170 Well #: 1-23

County: NESS

Total Vertical Depth: 2318 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: PO BOX 399

GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	4.5	2317	0	WITH 235 SX CMT TO SURFACE
------	-----	------	---	----------------------------

SURF	8.625	227		WITH 150 SX CMT
------	-------	-----	--	-----------------

75.34

Well Type: Gas UIC Docket No:

Date/Time to Plug: 03/03/2009 1:30 PM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: SCOTT CORSAIR

Company: AMERICAN WARRIOR

Phone: (785) 398-2270

Proposed Plugging Method: PUMP 200# HULLS WITH BOTTOM CMT AND FILL WITH CMT TO SURFACE. TIED ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/03/2009 2:45 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 200# HULLS & 150 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 500#. TIED ONTO BACKSIDE AND PRESSURED UP TO 600# IMMEDIATELY. NO CMT DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
2269	2274		
2212	2218		

INVOICED

DATE 3-20-09

INV. NO. 2009061341

RECEIVED

MAR 12 2009

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED

MAR - 6 2009

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)