

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23555-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 16-12S-20W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BITTEL Well #: 1-C
County: ELLIS Total Vertical Depth: 3995 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3985	0	w/725 sxs cmt
SURF	8.625	829	0	w/325 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2009 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 340 sxs 60/40 pozmix - 4% gel - 400# hulls.
Drilled down to approximately 1215' with mud pump and swivel - hit CH sand and junk in the hole.

Control # 20080062009

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2009 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 800'.
Poe RIH with tubing to 1200' - pumped 250 sxs 60/40 pozmix - 4% gel.
Tubing became sanded off in the hole.
Tubing twisted off - leaving 30 joints with a notch collar on the bottom.
Allied rigged to 4 1/2" casing - pumped 50 sxs cement with 250# hulls mixed in to circulate cement up 8 5/8" casing. Shut in 8 5/8".
Pumped an additional 40 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3918	3930		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 27 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #03278.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

K. WESLEY BITTEL

RT. #3
ELLIS, KS 67637


#1 "C" BITTEL

16-12-20W
SW SW SE

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOL _____ FIELD DIST 57 NO. EXT
(1/8 E)

ELV 2294 KB SPD 8/9/83 CARD ISSUED 6/7/84 # OIL WELL
MARM 3918-3930



API 15-051-23,555

LOG	Tops	Depth/Datum	
AL		1630	8 5/8 " 829 / 325SX, 4 1/2 " 3985 / 725SX
TOP	3348-1054		MICT - CO, PF (MARM) 3918-3930, W/2 SPF, AC 500G, RE-AC 3000G, SWB DWN & REC 6 BFPH (47% OIL), ONFU 1300' FL (400' GSY OIL ON TOP), FRAC 32,000# SD & FL (AMT NA), SWB DWN & REC 2.5 BFPH (50% OIL) / 6 HRS, FU 1300' FL (450' OIL), SWB DWN & REC 2 BFPH (50% OIL) / 2 HRS, FU 850' FL (400' OIL), SWB DWN & REC 1.5 BFPH (71% OIL), PF (LKC) 3895-3897, W/2 SPF, AC 500G (15%), SWB LD, NS, ONFU 125' FL (20' HO), POP
HEEB	3577-1283		
TOR	3597-1303		
LANS	3615-1321		
BKC	3860-1566		
MARM	3906-1612		
CONG	3941-1647		
RTD	3995-1701		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

NOTE: CORRECTION 4/12/84 - ORIGINALLY FIRST REPORTED AS N-B COMPANY AS OPERATOR, WESLEY BITTEL TOOK OVER OPERATIONS DURING COMPLETION

463°