

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23341-00-00
Spot: SESWNW Sec/Twnshp/Rge: 21-12S-20W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BITTEL Well #: 7
County: ELLIS Total Vertical Depth: 3914 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3913	0	w/unknown sxs cmt
SURF	8.625	914	0	w/375 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/20/2009 12:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 500# hulls.
Pulled 151 rods from well - tubing parted at 992'.
Tubing was open to perfs - decided to plug.
2" tubing in hole from 1000' - 3913'.
Control # 20080062007

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2009 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech shot two hole shot at 850'.
Allied rigged to casing - pumped 100 sxs neat 60/40 pozmix - followed with 225 sxs with 500# hulls to circulate cement up 8 5/8" casing to surface.
Shut in 8 5/8" casing - pumped an additional 50 sxs cement to pressure on 5 1/2" casing.
Max. P.S.I. 450#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3816	3822		


KANSAS CORPORATION COMMISSION
FEB 25 2009
RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #34895.

Plugged through: CSG

District: 04

Signed




(TECHNICIAN)

CM



N-B COMPANY, INC. 21-12-20W
 P.O. BOX 506 #7 BITTEL
 RUSSELL, KS 67665-0506 SE SW NW
 CONTR COMPANY TOOLS CTY ELLIS
 GEOL _____ FIELD DIST. 57 NO.
 ELV 2215 KB SPD 1/27/83 CARD ISSUED 4/28/83 W P 28 BOPD & TR WTR
 API 15-051-23,341 MARM 3816-3822



LOG	Tops	Depth/Datum
SC	1572 + 643
TOP	3250-1035
HEEB	3280-1065
TOR	3500-1285
LANS	3517-1302
BKC	3759-1544
ARB	3890-1675
RTD	3914-1699

8 5/8 " 914/375SX; 5 1/2 " 3913
 NO DST'S
 MICT - CO. PF (MARM) 3816-22, SWB DWN, NSO, AC 500G.
 SWB 3/4 BF (25% OIL) / 30", FU 300' MCO / 14 HRS, FRAC
 12,000# SD & NITROGEN, FU 2000' FL, SSO / 14 HRS, SWB 16
 BFPH (40% OIL), FU 1100' FL (65% OIL) / 14 HRS, SWB 6 BFPH
 (95% OIL) / 7 HRS, R&T, POP, P 28 BOPD & TR WTR, 3/20/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS