

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23150-00-00
Spot: SENWNW Sec/Twnshp/Rge: 21-12S-20W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BITTEL Well #: 5
County: ELLIS Total Vertical Depth: 3920 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3910	0	w/175 sxs cmt
SURF	8.625	813	0	w/250 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2009 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed: Ordered out 325 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.
Plugging: Junk in the hole - had to clean out from 200' to 2200'.
Method: No records - need to perf salt at 2200' - anhy at 1625' and 775'.

Control # 20080062005

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2009 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 2200' - 1625' - 775'.
Ran tubing to 3200'. Allied pumped 10 sxs gel spacer - followed with 40 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled to 1120'. Allied pumped 265 sxs cement with 200# hulls - circulated cement out 4 1/2" and 8 5/8".
PTOH. Allied pumped 20 sxs cement - casing full.

Perfs:

Top	Bot	Thru	Comments
3828	3836		

FEB 25 2009

Remarks: ALLIED CEMENTING COMPANY.

RECEIVED

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3

FEB 23 2009

N-B COMPANY, INC.
P.O. BOX 506

#5 BITTEL

21-12-20W
SE NW NW

RUSSELL, KS 67665-0506

CONTR EMPHASIS OIL OPERATIONS

CITY ELLIS

GEOLOGICAL

FIELD DIST 57 NORTH

ELV 2222 KB SPD 9/11/82


CARD
ISSUED

11/18/82

WELL P 20 BOPD

MARM 3828-3836

API 15-051-23,150



LOG	Top	Depth/Datum
HEEB		3489-1267
TOR		3509-1287
LANS		3527-1305
BKC		3779-1557
MARM		3818-1596
CONG		3859-1637
ARB		3892-1670
RTD		3920-1698

8 5/8 - 813/250SX; 4 1/2 - 3910/125SX

DST (1) 3894-3906 (ARB) / 30-30-15-15, REC 5' WM, SIP 50-30#, FP 20-20 / 20-20#

MICT - CO, PF (MARM) 3828-3836 W/4 SPF, AC 500G, FRAC W/ NITROGEN & 12,000# SD, R&T, POP, P 20 BOPD (GR 37"), 10/6/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS