

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21530-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 21-12S-20W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BITTEL OWWO Well #: 1
County: ELLIS Total Vertical Depth: 1631 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1631	0	w/400 sxs cmt
SURF	8.625	215	0	w/140 sxs cmt

Well Type: SWD UIC Docket No: D21281.0 Date/Time to Plug: 02/25/2009 11:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 500# hulls.
Backside cemented top to bottom.
Packer stuck in bottom of the hole.

Control # 20080062001

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2009 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 4 1/2" casing with a swedge and valve - pumped 160 sxs 60/40 pozmix - 4% gel with 500# hulls mixed in.
Max. P.S.I. 900#. S.I.P. 700#.

Perfs:

Top	Bot	Thru	Comments
1620	1629		Cedar Hills

RECEIVED
MAR 2 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34898.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

FEB 26 2009



N-B COMPANY, INC.

'OWWO'

21-12-20W

P.O. BOX 506

#1 BITTEL

NW SW NW

RUSSELL, KS 67665-0506

CONTR EMPHASIS OIL OPER. CTY ELLIS

GEOL _____ FIELD DIST 57 NORTH

E 2232 KB CM 7/26/82 CARD ISSUED 9/9/82 IP SWDW

CED HILLS 1620-29

API 15-851-21,530-A

+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
-----	------	-------	-------

ANH		1591 +	641
TOP		3269	-1037
HEEB		3499	-1267
TOR		3521	-1289
LANS		3538	-1306
BKC		3782	-1550
MARM		3834	-1602
CONG		3872	-1604
ARB		3925	-1693
RTD		3932	-1700

OLD INFO: OPERATOR WAS N-B CO., INC. #1 BITTEL, SPD 8/5/75, SET 8 5/8" 215/140SX, COMP AS D&A/ARB 8/17/78, CONTR: EMPHASIS OIL OPERATIONS

NEW INFO: RE-ENTERED 7/26/82; WSH DWN TO 3928', SET 4 1/2" 1631/400SX, MICT - CO. PF (CED HILLS) 1620-29, INJECTION RATE SATISFACTORY, SWDW

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS