

15-195-21013-00-00 11-18

6 031191

API NUMBER 15- 195-21,013-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE SE SW, SEC. 1, T 11 S, R 23 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767 Lease Name Ninemire Well # A-1

Operator: Ritchie Exploration Inc. County Trego 127.43
Name & Address 125 N. Market Suite 1000
Wichita, Ks. 67202

Well Total Depth 3921 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 214

Abandoned Oil Well X Gas Well _____ Shut Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 18 Month: Nov Year: 19 88

Plugging proposal received from Duntz

(company name) Kelso (phone) _____

were: 8 5/8" set at 214' w/185 sks. 4 1/2" set at 3912' w/175 sks.

Perf 3550' - 36' - 38'. Order sand and Common Cement. Pull pipe.

Order 200 sks 65/35 Poz 10% Gel 2% Dicel 500# Hulls. Allied Cement Co. Rush Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:50AM Day: 18 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3500' w/4 sks Common Cement on sand w/bailer.

Recovered 1800' of 4 1/2" casing w/shots also at 2200' and 2400'. Squeezed 8 5/8" w/200 sks cement w/500# Hulls mixed into max psi 500#. Close in at 150# psi. Plug complete.

Wireline ran to anhydrite.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICE observe this plugging.

DATE 1-19-89

INV. NO. 23668

Sib S.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow