

15-195-20811-00-00 11-18

6 031192

API NUMBER 15- 195-20,811-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2N/2SE, SEC. 3, T 11 S, R 23 W/E
2310 feet from S section line

TECHNICIAN'S PLUGGING REPORT

1320 feet from E section line

Operator License # 4767

Lease Name Harger Well # C-1

Operator: Ritchie Exploration Inc.
Name & Address: 125 N. Market Suite 1000
Wichita, Ks. 67202

County Trego 129.06
Well Total Depth 3971 feet

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1989

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 206

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casting & Pumping License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 18 Month: Nov Year: 19 88

Plugging proposal received from Duntz

(company name) Kelso (phone) _____

were: 8 5/8" set at 706' w/185 sks. 4 1/2" set at 3896' w/125 sks. Perfs 3694' - 97'.

Order sand and Common Cement. Pull pipe. Order 65/35 Poz 10% Gel 2% Dicel 500# Hulls.
Allied Cement Co. Rush Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15AM Day: 18 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3650' w/4 sks Common Cement on sand w/bailer.

Recovered 2000' of 4 1/2" casing w/shots. Also, at 2200' and 2400'. Squeezed 8 5/8" w/200
sks cement w/500# Hulls mixed into max psi 700#. Close in psi 200#. Plug complete.

Wireline ran to anhydrite.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 1-19-89

J.S.

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 23667