

15-195-21202-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-195-21,202-00-00

SE, Sec. 3, T 11 S, R 23 W/E

1650 feet from N/E section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name HARGER C Well # D-2

Operator: A. SCOTT RITCHIE  
Name & Address 125 N. MARKET SUITE 950  
WICHITA, KS.

County TREGO

Well Total Depth 3869 feet \$125.74

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor MURFIN DRLG CO. License Number 611

Address 617 UNION CENTER BLDG. WICHITA

Company to plug at: Hour: Day: Month: 4 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO TERRY McRAE

(company name) MURFIN DRLG CO. (phone)

were: 20 SX @ 1720 CIRC. 10 MIN. WITH HEAVY MUD

90 SX @ 875

40 SX @ 250

10 SX @ 40 SOLID BRIDGE PLUG

ALLIED CEM. 10 SX RATHOLE 10 SX MOUSE HOLE

CEM. > 50/50 POZ 6% GEL 3% CC Signed Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 AM Day: 25 Month: 4 Year: 19 83

ACTUAL PLUGGING REPORT

AS ABOVE

RATHOLE WAS CEMENTED IN WHEN SURFACE PIPE WAS SET.

DUG DOWN AND CUT OFF TOP OF RATHOLE. FILLED WITH CEM.

Remarks: ELEV. 2233 KB

ANHY. 1713-58

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 5-4-83

INV. NO. 4186-W

RECEIVED STATE CORPORATION COMMISSION

5-2-1983  
MAY 02 1983

CONSERVATION DIVISION  
Wichita, Kansas

Signed Carl Goodrow  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82