

15-195-21722-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,722-00-00

LEASE NAME Nicholson "B"

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

3140 Ft. from E Section Line

LEASE OPERATOR Energy Reserves Group, Inc.

SEC. 24 TWP. 11S RGE. 21 (X) or (W)

ADDRESS 925 Patton Road, Great Bend, KS 67530

COUNTY Trego

PHONE# (316) 792-2756 OPERATORS LICENSE NO. 5318

Date Well Completed 5-23-85

Character of Well D & A

Plugging Commenced 5-23-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-23-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 3,950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	271.92'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st Plug @ 3840' w/20 sx cement; 2nd Plug @ 1700' w/20 sx cement; 3rd Plug @ 950' w/100 sx cement & 1 sx Floseal; 4th Plug @ 325' w/40 sx cement; Bridge Plug from 40' to 0' w/ 10 sx cement; 10 sx cement in rat hole (Plugs calculated by displacement) Total cmt used 200 sx 50/50 Pozmix, 6% Gel, 3% CC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1100 E. 8th, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Barton

RECEIVED
STATE CORPORATION COMMISSION

6-4-1985
JUN 04 1985

Jim W. Sullivan, District Engineer (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God.

(Signature) Jim W. Sullivan

(Address) 925 Patton Rd, Great Bend, KS 57630

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 85

Ronald E. Rowe
Notary Public

My Commission Expires: My Appt. Exp. Sept. 9, 1987

