

15-195-21617-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,617-00-00

LEASE NAME Armbrister

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 34 TWP. 11 RGE. 21 (E) or (W)

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS 505 Fourth Financial Center, Wichita, Ks. 67202

COUNTY Trego

PHONE# (316) 265-6697 OPERATORS LICENSE NO. 5141

Date Well Completed 11-4-84 (Rotary)

Character of Well _____

Plugging Commenced 8-28-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-28-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top 3611 Bottom 3843 T.D. 4027

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Kansas City	Oil & Water	3674	78	8 5/8	266	None
Kansas City	Oil & Water	3611	14	4 1/2	4019	None
				E. O. Tool @ 1822' cemented to surface with 350 SX Halco Lite Cement		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Halliburton connected to annulus and pumped in 5 bbls. of cement slurry and pressured to 500# and held. Connected to 4 1/2" casing and mixed hulls and 175 sacks of Econolite Cement and pressured 1000# and held steady. State plugger on job was Dennis Hammel. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Zenith Drilling Corporation License No. 5141

Address 505 Fourth Financial Ctr., Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Sherrill Compton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sherrill Compton
Sherrill Compton, Vice President

(Address) 505-4th Financial Ctr., Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 4th day of Sept., 19 86

Sharon R. Allen
Sharon R. Allen Notary Public


My Commission Expires: 12-15-88



9-8-1986
SEP 8 1986

15-195-21617-00-00

D N B Drilling, Inc.



J. L. DONELSON, PRES.
(316) 687-5471

535 NORTH OLIVER

WICHITA, KANSAS 67208

ROTARY CONTRACTOR DRILLING DEALS

DRILLERS' LOG

Zenith Drilling Corporation
Suite 505 Fourth Financial Center
Wichita, Kansas 67202

Armbrister #1
SE SW NW Sec. 34-11-21W
Trego County, Kansas

Commenced: 10-26-84
Completed: 11-5-84

Surface Casing: Ran 6 jts. 8 5/8" 20# new casing, tallied 258',
set @ 266. Cemented w/200 sx 60/40 pozmix, 2%
gel, 3% cc. Cmt. did circ. Plug down @ 6:45 PM.


FORMATION

DEPTH

Sand & Shale	0-631
Shale	631-1759
Anhydrite	1759-1804
Shale	1804-3060
Shale & Lime	3060-3350
Lime	3350-4027 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB Drilling, Inc.

By 

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 8th day of November, 1984.

Gwen Hinderliter, Notary Public

My appointment expires:
January 11, 1988



9-8-1986
SEP 8 1986