

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Trego County, Sec. 35 Twp. 11S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Christie-Stewart Drilling Company

Lease Name Spilker Well No. 1

Office Address 611 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 3, 19 63

Application for plugging filed March 3, 19 63

Application for plugging approved March 3, 19 63


Plugging commenced March 3, 19 63

Plugging completed March 3, 19 63

Reason for abandonment of well or producing formation Non-productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation - Depth to top - Bottom - Total Depth of Well 3756 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud, spotted 25 sx cement at 600 feet, 25 sx cement at 200 feet, set plug at 40 feet with 1/2 sx cotton seed hulls on top, 10 sx cement in top of hole, 10 sx cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 1963
3-6-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Christie-Stewart Drilling Co.

Address 611 Union Center

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
ROBERT C. LEWELLYN (employee of owner) or (owner/representative)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert C. Lewellyn

611 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of March, 1963

Patricia Hotmar
Patricia Hotmar Notary Public.

My commission expires January 19, 1964



15-195-00485-00-00

WELL LOG

Company:	Christie-Stewart Drilling Co.	Sec: 35-11S-21S
FARM:	Spilker No. 1	Loc: NW NE NE
Rig:	No. 1	County: Trego
Total Depth	3756	State: Kansas
Comm:	2-22-63	Comp: 3-3-63
Contractor:	Christie-Stewart Drilling Co.	Elevation: 2304 KB
Casing	8 5/8 @ s10 KBM/175 SX	Production: D & A

670'	Surf soils, clays, bkn sd & sh.	3532'	Chalky limestone
1750'	Bkn sd & sh.	3550'	Gray sh.
1790'	Anh	3577'	Cherty limestone.
2100'	Sh.	3591'	Gray sh.
2367'	Bkn sd.	3599'	White limestone
2832'	Bkn shale & limestone.	3604'	Gray sh.
3123'	Bkn sd and limestone.	3632'	White limestone, wtr.
3278'	Bkn Limestone.	3639'	Gray sh.
3304'	Bkn Limestone & shale.	3655'	White limestone
3355'	Sh. & shells.	3663'	Gray sh
3374'	White limestone	3688'	White limestone
3388'	Gray shale.	3702'	Broken sh.
3431'	White limestone, bkn.	3738'	Buff limestone
3454'	Gray sh.	3746'	Gray sh.
3490'	Buff limestone	3756'	White limestone
3505'	gray sh.	3756'	TD

FORMATION TOPS

Topeka	3355'	(-1051')
Heebner	3568'	(-1264')
Toronto	3591'	(-1287')
Lansing	3604'	(-1300')
TD	3756'	(-1452')

DRILL STEM TESTS

Test Number 1 - March 2, 1963, 3610-38, 1½ hours, very weak blow through test, recovered 80 feet salt water. ISIP 1175#, FSIP 1046W, FP 19 to 56#.

RECEIVED
STATE CORPORATION COM.
3-6-1963
MAR 6 1963

CONSERVATION
Wichita, Kansas