

15-195-22201-00-00

LEASE NAME Bodine

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4515 Ft. from S Section Line

4840 Ft. from E Section Line

SEC. 35 TWP. 11S RGE. 21W (X) or (W)

COUNTY Trego

Date Well Completed 5/30/2000

Plugging Commenced 12:00PM 5/30/00

Plugging Completed 3:30PM 5/30/00

LEASE OPERATOR DENIS ROBERTS OIL

ADDRESS 3904 Fairway Drive Hays, Kansas 67601

PHONE# (785) 625-8526 OPERATORS LICENSE NO. 32322

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/28/00 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4003

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	212	8 5/8	211.98	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

1st Plug @ 3940'W/25sks 5th Plug @ 40'W/40sks Circulated 1st Plug 15 Minutes with 48Vis Mud  
2nd Plug @ 1760'W/25sks 10 sks In Mouse Hole Plugs displaced with mud  
3rd Plug @ 1000'W/100sks 15sks In Rat Hole Total 225sks 60/40Poz 6%Gel By Allied Cementing  
4th Plug @ 265'W/40sks Completed @ 3:30PM 5/30/2000

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Denis Roberts Oil AUG 17 2000

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss. 8-17-2000

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3904 Fairway Dr Hays KS



TO before me this 14th day of Aug 2000

Notary Public

My Commission Expires: 8/11/2003

USE ONLY ONE SIDE OF EACH FORM

