


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-195-20291-00-01

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Trego County. Sec. 2 Twp. 11 Rge. 22 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C SW NW  
Lease Owner Don E. Pratt  
Lease Name Hilgers #1 Well No.  
Office Address Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2/16/79 19  
Plugging completed 2/23/79 19  
Reason for abandonment of well or producing formation  
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 3900  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	253	none
				4 1/2"	2888	2958

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Pushed plug to 3300' and ran 3 sacks cement. Loaded hole, shot pipe at 2965', pulled  
18 joints and ran into yellow wrap. Hembree Well Service pulled yellow wrap, total of  
53 joints. Pumped 3 sacks hulls, 70 sacks 50-50 pos, 6%, 9 sacks gel, released  
plug 8-5/8, 60 sacks cement, 50-50 pos, 6%. Had surface pipe cut off and collar  
welded on.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

*R. Darrell Kelso*  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 79

My commission expires



*Margaret Melcher*  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
3-5-1979  
MAR - 5 1979  
CONSERVATION DIVISION  
Wichita, Kansas

15-195-20291-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
10-16-1978  
OCT 16 1978

CONSERVATION DIVISION  
Wichita, Kansas

CORRECTED CARD

F & M OIL CO., INC. #1 HILGERS 2-11-22  
603 UNION CENTER, WICHITA, KS. C SW NW  
CONTR ABERCROMBIE DRLG. CTY TREGO  
GEOL GENE FALKOWSKI FIELD DEMURRY  
E 2179 KB CM 10/19/77 <sup>CARD</sup> ISSUED 11/7/74 IP D&A/CONG  
10/28/74

API 15-195-20,291

LOG	TOPS	DEPTH	DATUM
ANH		1658	+ 521
B ANH		1701	+ 478
HEEB		3421	-1242
TOR		3443	-1264
LANS		3460	-1281
BKC		3699	-1520
MARM		3766	-1587
CONG CHT		3820	-1641
LTD		3900	-1721

8 5/8" 253/150sx  
DST (1) 3446-3510 / 30-30-30-30, REC 160' GIP, 140' O&GCM, BHP 837-763#  
FP 65-112#  
DST (2) 3510-3538 / 20-20-20-20, REC 5'M, BHP 25-25#, FP 25-25#  
DST (3) 3539-3555 / 45-30-45-30, REC 330'W, BHP 883-883#, FP 12-149#  
DST (4) 3585-3660 / 45-30-45-30, REC 330' GIP, 150' O&GCM, 60' VHO&GCM, BHP 1114-1068#, FP 65-140#  
DST (5) 3770-3800 / 30-30-30-30, REC 15' SOCM, BHP 976-883#, FP 28-46#

CORRECTED CARD: 11/14/74  
TOP WAS: TOP 3443  
TOP IS : TOR 3443

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

DON E. PRATT 2-11-22W 24  
P. O. BOX 370 #1 HILGERS "OWWO" C SW NW  
HAYS, KS.

CONTR MURFIN DRILLING CO. CTY TREGO  
GEOL \_\_\_\_\_ FIELD DEMURRY

E 2179 KB CM 8/15/77 <sup>CARD</sup> ISSUED 12/22/77 IP D&A/CONG CHT

API 15-195-20,291A

LOG	TOPS	DEPTH	DATUM
ANH		1658	+ 521
B/ANH		1701	+ 478
HEEB		3421	-1242
TOR		3443	-1264
LANS		3460	-1281
BKC		3699	-1520
MRM		3766	-1587
CONG CHT		3820	-1641
LTD		3900	-1721

OLD INFO: WAS F & M OIL CO. #1 HILGERS, SPD 10/19/74; 8-5/8" 253/150sx; D&A/CONG 10/28/74  
DST (1) 3446-3510/30-30-30-30, 160' GIP, 140' O&GCM, SIP 837-763#, FP 65-112#  
DST (2) 3510-3538/20-20-20-20, 5'M, SIP 25-25#, FP 25-25#  
DST (3) 3539-3555/45-30-45-30, 330'W, SIP 883-883#, FP 12-149#  
DST (4) 3585-3660/45-30-45-30, 330' GIP, 150' O&GCM, 60' VHO&GCM, SIP 1114-1068#, FP 65-140#  
DST (5) 3770-3800/30-30-30-30, 15' SOCM, SIP 976-883#, FP 28-46#

RE-ENTERED 8/15/77, SET 4 1/2" 3893/175sx;  
MICT - CO, PF (MARM) 16/3766-(OVER)

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS