

15-195-21238-00-00

API NUMBER 15-195-21,238-00-00

LEASE NAME Hilgers

WELL NUMBER B #1

660 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP. 11SRGE. 22W (E) or (W)

COUNTY Trego

Date Well Completed 7/28/83

Plugging Commenced 9/30/93

Plugging Completed 9/30/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Grady Bolding Corporation

ADDRESS P. O. Box 486, Ellinwood, KS. 67526

PHONE (316) 564-2240 OPERATORS LICENSE NO. 7383

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/30/93 (date)

by Marion Schmidt (on location) (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Marmaton Depth to Top 3784 Bottom 3788 T.D. 3850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Production Casing	Surface	3850	5 1/2"	3850	none

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 7 1993  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Perforated casing (one shot) at 800', 1670' and 2420'. Ran Tubing to 3619' and spotted 25 sacks cement with 100# hulls. Displaced with 13 bbls water. Pulled tubing to 3403' and pumped 9 sacks Gel with 150# hulls. Displaced with 9 bbls water. Pulled tubing to 2420 and pumped down 100 sacks cement with 150# hulls. Displaced with 4 bbls water. Pulled tubing to 890' and pumped 55 sacks cement. cement circulated to surface. Tied on to annulus and squeezed with 75 sacks cement and 50# hulls. Maximum pressure 100#. Shut in pressure 50# Tied onto 5 1/2" casing and squeezed with 45 sacks cement.

Name of Plugging Contractor Maximum pressure 400# shut in pressure 100# Total cement 300 sacks 10% Gel  
Address Allied Cementing Company, Russell, KS. 67665 Total hulls 4 sacks Total Gel 9 sacks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Grady Bolding (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Grady Bolding

(Address) P. O. Box 486 Ellinwood, KS. 67526

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1993

JENNY KASSELMAN  
State of Kansas  
My Appt. Exp. 7-16-94

Jenny Kasselmann  
Notary Public

My Commission Expires: 7-16-94

USE ONLY ONE SIDE OF EACH FORM