

MAR 30 2009

CONSERVATION DIVISION
WICHITA, KS

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1

March 2009

This Form must be Typed

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 5252
Name: R. P. Nixon Operations, Inc.
Address 1: 207 W. 12th St.
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Duane Achterberg
Phone: (785) 656-0038

API No. 15 - 167-01643-00-01
If pre 1967, supply original completion date: 9-13-62
Spot Description: _____
NE - SE - SW. Sec. 24 Twp. 15 S. R. 12 East West
990 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Russell
Lease Name: Woydziak Well #: 1

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: none Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 260 Cemented with: 150 Sacks
Production Casing Size: 5 1/2 Set at: 3324 Cemented with: 125 Sacks

List (ALL) Perforations and Bridge Plug Sets:

2926-30 3007-09 3031-34 3081-84 3193-96 3298-3302 CIBP @ 3255

Elevation: 1852 (G.L. / K.B.) T.D.: 3332 PBDT: 3306 Anhydrite Depth: 764
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Plug down the casing if permissible. FL 23 seconds dropping a rock. No casing leak, uneconomical to produce. All options exhausted. Otherwise as KCC recommendations.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Too Old

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Duane Achterberg

Address: 207 W. 12th City: Hays State: Ks Zip: 67601 + _____

Phone: (785) 656-0038

Plugging Contractor License #: 5252 Name: R.P. Nixon Operations, Inc.

Address 1: 207 W. 12th St. Address 2: _____

City: Hays State: Ks Zip: 67601 + _____

Phone: (785) 628-3834

Proposed Date of Plugging (if known): As soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-26-09 Authorized Operator / Agent: Duane Achterberg
(Signature)

Duane Achterberg
PKF

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- H-30, INC.
Farm- Woydziak No. 1

SEC. 24 T. 15 R. 12W
NE SE SW

Total Depth. 3332'
Comm. 9-13-62 Comp. 9-23-62
Shot or Treated.
Contractor.
Issued. 11-17-62

County Russell
KANSAS



Elevation. 1049' DE

Production. DRY

CASING:

8 5/8" 260' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface soil	10
gravel, rock & streaks iron	90
sand streaks, shale & iron	150
shale	260
shale & shells	388
sand & pyrite	402
red bed shale w/sand streaks	730
red bed	733
anhydrite	764
shale & shells	1350
lime & shale	2150
shale w/lime streaks	2260
shale & lime	2595
lime & shale	3008
lime	3037
lime & shale	3099
Kansas City lime	3214
lime & shale	3332 RTD
Total Depth	

TOPS: ELECTRIC LOG

Topeka	2613
Haebner	2902
Toronto	2913
Brown Lime	2992
Lansing	3002
Base Kansas City	3214
Conglomerate	3296
Arbuckle	3306

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 30 2009
CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

NIXON, R P OPERATIONS, INC
207 W 12TH
HAYS, KS 67601-3810

April 02, 2009

Re: WOYDZIAK #1
API 15-167-01643-00-01
24-15S-12W, 990 FSL 2310 FWL
RUSSELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 29, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550