

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 129-20677 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Spud date: 9/15/1983

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334
(Owner / Company Name) (Operator's)

Address: P.O. Box 18496 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 879 - 9375

Lease: Stoops "A" Well #: 1-19 Sec. 19 Twp. 32 S. R. 42 East West

E/2 - SE - SW Spot Location / QQQQ County: Morton

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1985 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" 24# J-55 Set at: 1,478' Cemented with: 700 Sacks

Production Casing Size: 5 1/2" 14# J-55 Set at: 5,351' Cemented with: 240 Sacks

List (ALL) Perforations and Bridgeplug Sets: Marmaton 3,706 - 3,714.

Elevation: 3,561' (G.L. / K.B.) T.D.: 5,351' PBTD: 5,339' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See attached sheet

RECEIVED
KANSAS CORPORATION COMMISSION
APR 01 2009
CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bud Neff, Production Superintendent Phone: (620) 277 - 0803 ext. 11

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: _____
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): 3-17-09 8:00

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 3/31/09 Authorized Operator / Agent: Aletha M. Devore-King (Signature) Dist 1

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

~~Handwritten signature and scribbles at the bottom left.~~

Handwritten signature/initials at the bottom right.

Stoops 'A' 1-19
Plug and Abandon

Procedure:

1. MIRU workover unit, and dig out bradenhead. TOOH with any rods and or tubing that is in the hole. Lay tubing and rods out in singles. RIH with sand line, tag TD. Order out 2-3/8" 4.7# J-55 workstring, length based on TD determined above.
2. MIRU wireline unit, crane, and grease. PU 5 1/2" CIBP and setting tool, RIH and set CIBP at $\pm 3,650'$. Dump 5 sx of cement on CIBP, POOH. If unable to get CIBP to $\pm 3,650'$, TOOH w/ CIBP, TIH w/ 2-3/8" TBG to $\pm 3,540'$, mix cement & pump 3 sx cotton seed hulls and 50 sx cement, POOH.
3. NU 5-1/2" pull sub, work 5-1/2" CSG out of slips & pull freepoint on CSG. RIH with WL and tools, cut CSG above freepoint (minimum cut: 1,530'). POOH and RDMO WL. Rig up on 5 1/2" casing, open surface valve and attempt to establish circulation up 8-5/8" x 5 1/2" annulus. If circulation is achieved, mix and pump 75 sx cement for stub plug/ surface CSG shoe plug. TOOH w/ 5-1/2" CSG laying down.
4. TIH w/ 2-3/8" TBG to check TOC after cement has had time to set up. If TOC is less than 1,425', mix & pump 40 sx cement to finish out surface CSG plug. TOOH w/ TBG to 550', mix and pump 40 sx cement of cement for the useable water horizon plug. TOOH w/ TBG to 40', mix and pump 10 sx cement to surface for surface plug.
5. Cut off casing 4 ft. below ground level and weld on steel ID plate. RDMO WOR.
6. Remove all production equipment and restore well site to original condition.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 01 2009

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., LLC. 50571

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: L. BEAL KS

DATE <u>3-17-09</u>	SEC. <u>19</u>	TWP. <u>32</u>	RANGE <u>42 W</u>	CALLED OUT	ON LOCATION	JOB START <u>3:00pm</u>	JOB FINISH <u>6:00pm</u>
LEASE <u>Stoops</u>	WELL <u>A1-19</u>	LOCATION <u>ELKART KS 15N 2W</u>	COUNTY <u>MOHAWK</u>		STATE <u>KS</u>		
OLD OR NEW (Circle one)				<u>IS 1/2 E N into</u>			

CONTRACTOR SUPERIOR #6
 TYPE OF JOB PTA (old well)
 HOLE SIZE 7 7/8 T.D.
 CASING SIZE 5 1/2 14 8 1/2 DEPTH TD - 1500'
 TUBING SIZE 2 3/4 4 1/2 DEPTH 3550
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX 2000 MINIMUM 0
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG.
 PERFS.
 DISPLACEMENT

OWNER SAME
 CEMENT AMOUNT ORDERED 125 SK
60/40 4 1/2" O.C.

EQUIPMENT

PUMP TRUCK CEMENTER BOB
 # 471/469 HELPER FRANK D
 BULK TRUCK
 # 472/468 DRIVER MARCO
 BULK TRUCK
 # DRIVER

COMMON	@		
POZMIX	@		
GEL	@	<u>20⁰⁰</u>	<u>1248⁰⁰</u>
CHLORIDE	@		
ASC	@		
	@	<u>125 SK</u>	<u>1405</u>
	@	<u>25K HULL</u>	<u>3185</u>
	@		<u>1756²⁵</u>
	@		<u>6320</u>
	@		
	@		
	@		
	@		
	@		
HANDLING	@	<u>190</u>	<u>2.40</u>
MILEAGE	@	<u>10.5K mi</u>	<u>456⁰⁰</u>
			<u>1520⁰⁰</u>
			<u>5043.95</u>

REMARKS:
Mix 50 SK @ 3550'
Mix 75 SK @ 1530'

CHARGE TO: CHESAPEAKE
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB 3530'
 PUMP TRUCK CHARGE 1315⁰⁰
 EXTRA FOOTAGE @
 MILEAGE 80 @ 7⁰⁰ 560⁰⁰
 MANIFOLD
Stand by hours 4 @ 250⁰⁰ 1000⁰⁰
 TOTAL 2875⁰⁰

RECEIVED
 KANSAS CORPORATION COMMISSION
 PLUG & FLOAT EQUIPMENT

APR 01 2009

CONSERVATION DIVISION
 WICHITA, KS

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME JOHN TRACY
 SIGNATURE John Tracy

TOTAL _____
 SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

ALLIED CEMENTING CO., LLC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
L. Bend Ks

DATE <u>3-18-09</u>	SEC. <u>19</u>	TWP. <u>32</u>	RANGE <u>42W</u>	CALLED OUT	ON LOCATION	JOB START <u>12:00</u>	JOB FINISH <u>1:30</u>
LEASE <u>Top</u>	WELL # <u>A-1-19</u>	LOCATION <u>ELBERT KS 18N</u>			COUNTY <u>Morr</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>OLD</u>		<u>2W 15 1/2 E Note</u>					

CONTRACTOR Superior #6
 TYPE OF JOB PTA (old well)
 HOLE SIZE 7 7/8 T.D.
 CASING SIZE 5 1/2 DEPTH 1500/3550
 TUBING SIZE 2 1/2 46 DEPTH 3550
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX 200 PSI MINIMUM 0
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG.
 PERFS.
 DISPLACEMENT

OWNER Same
 CEMENT
 AMOUNT ORDERED 90 SK
60/40 40% @

COMMON	@	
POZMIX	@	
GEL	@	
CHLORIDE	@	
ASC	@	
<u>90 SK LITE</u>	@ <u>14/85</u>	<u>126450</u>
	@	
	@	
	@	
	@	
	@	
	@	
HANDLING <u>93</u>	@ <u>2.40</u>	<u>223.00</u>
MILEAGE <u>10.5 km</u>		<u>744.00</u>
TOTAL		<u>2231.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bob
 # 421/469 HELPER Kenneth / FRANKLIN
 BULK TRUCK
 # 422/468 DRIVER MAGO
 BULK TRUCK
 # DRIVER

REMARKS:

Pup 10BBL GEL HD -
Mix 40SK @ 1530'
Mix 40SK @ 550'
Mix 10SK @ 40-0'
WASH UP
Circ cut to surface
TOP OFF CSG

SERVICE

DEPTH OF JOB	<u>1530'</u>
PUMP TRUCK CHARGE	<u>1017.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>80 mi</u>	@ <u>N/C</u>
MANIFOLD	@ <u>TRUCK ON LOC</u>
	@
	@
TOTAL <u>1017.00</u>	

CHARGE TO: Chesapeake
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT
 RECEIVED
 KANSAS CORPORATION COMMISSION
APR 01 2009
 CONSERVATION DIVISION
 WICHITA, KS
 @ _____
 @ _____
 @ _____
 @ _____
 TOTAL _____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME John Tracy
 SIGNATURE John Tracy

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS