


15-195-20787-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County. Sec. 3 Twp. 11S Rge. 23W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE NE SW
Lease Owner Zenith Drilling Corporation
Lease Name SCHABEN #1 Well No. #1
Office Address Suite 505, Fourth Financial Center, Wichita KS
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed April 14 1981
Application for plugging filed April 14 1981
Application for plugging approved April 14 1981
Plugging commenced April 14 1981
Plugging completed April 14 1981
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Set 1st Plug @ 900' with 60 sacks.
Set 2nd Plug @ 220' with 30 sacks;
Set 3rd Plug @ 40' to Solid Bridge with 10 sacks,
5 sacks in rathole, 50-50 posmix, 6% gel.

Job was completed @ 12:45 p.m., 4/14/81.
State Pluggger - Gilbert Balthazar.

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1981

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



15-195-20787-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Zenith Drilling Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	SCHABEN #1
LOCATION:	C NE NE SW, Section 3-11S-23W Trego County, Kansas
SPUD DATE:	4/07/81
COMPLETION DATE:	4/14/81

0	210	Sand & Shale
210	702	Shale
702	1290	Sand & Shale
1290	1520	Ceder Hills Sand
1520	1787	Shale
1787	1815	Anhydrite
1815	3473	Shale
3473	3940	Lime & Shale
	3940	Rotary Total Depth

Spud @ 2:00 p.m., 4/07/81. Drilled 210' of a 12 1/2" hole. Ran 5 jts. of 8 5/8" - 20# casing (tally 199.78) Set @ 206.79. Cemented with 150 sacks of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 6:50 p.m., 4/07/81.

RID @ 3940'. Set 1st Plug @ 900' with 60 sacks. 50-50 posmix, 6% gel. Set 2nd Plug @ 220' with 30 sacks, 50-50 posmix, 6% gel. Set 3rd Plug @ 40' to surface solid bridge with 10 sacks, 50-50 posmix, 6% gel. 5 sacks in rathole. Job was completed @ 12:45 p.m., 4/14/81. State Plugger - Gilbert Balthazar.

SAMPLE TOPS:

Anhydrite 1783'
B/Anhydrite 1815'


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHABEN #1, C NE NE SW, Section 3-11S-23W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of April, 1981.



Suzanne M. Hofer
Suzanne M. Hofer, Notary Public
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
4-22-1981
APR 22 1981
DIVISION

2-4-85