


15-195-2092-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Trego County, Sec. 3 Twp. 11S Rge. 23W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
150' SW of C SW NE NE  
Lease Owner K & E Petroleum, Inc.  
Lease Name SCHABEN #2 Well No. #2  
Office Address Hardage Center, Suite 300, 100 S. Main, Wichita,  
Character of Well (Completed as Oil, Gas or Dry Hole) KS 67202



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed May 19 1981  
Application for plugging filed May 19 1981  
Application for plugging approved May 19 1981  
Plugging commenced May 19 1981  
Plugging completed May 19 1981

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar  
Producing formation Depth to top Bottom Total Depth of Well 3750'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. @ 3750'  
Set 1st Plug @ 1700' with 60 sx.  
Set 2nd Plug @ 340' with 35 sx.  
Set 3rd Plug @ 40' Solid Bridge with 10 sx.  
5 sx. in rathole, 50-50 posmix, 6% gel.

Plug down @ 11:45 p.m., 5/19/81.  
State Plugger - Gilbert Balthazar.

RECEIVED  
STATE CORPORATION COMMISSION  
5-29-1981  
MAY 29 1981

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc. CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1981

Suzanne M. Hofer  
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



15-195-20792-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	K & E Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	SCHABEN #2
LOCATION:	150' SW of C SW NE NE, Section 3-11S-23W Trego County, Kansas
SPUD DATE:	5/12/81
COMPLETION DATE:	5/19/81

0	319	Clay & Sand
319	703	Shale & Sand
703	1739	Sand & Shale
1739	1797	Anhydrite
1797	3522	Shale
3522	3544	Lime & Shale
3544	3608	Shale
3608	3645	Lime
3645	3750	Shale & Lime
	3750	Rotary Total Depth

Spud hole @ 10:15 a.m., 5/12/81. Drilled 319' of a 12 1/4" hole. Ran 8 joints of 8 5/8" - 20# casing (tally 311.26) Set @ 316' K.B. Cemented with 220 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug down @ 5:30 p.m., 5/12/81. Drilled plug @ 1:30 a.m., 5/13/81.

T.D. @ 3750'. Set 1st Plug @ 1700' with 60 sx., Set 2nd Plug @ 340' with 35 sx., Set 3rd Plug @ 40' Solid Bridge with 10 sx., 5 sacks in rathole, 50-50 posmix, 6% gel. Plug down @ 11:45 p.m. 5/19/81. State Plugger - Gilbert Balthazar.

SAMPLE TOPS:

Anhydrite 1750'  
B/Anhydrite 1797'

RECEIVED  
STATE CORPORATION COMMISSION  
5-29-1981  
MAY 29 1981

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )


CONSERVATION DIVISION  
Wichita, Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHABEN #2, 150' SW of C SW NE NE, Section 3-11S-23W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*  
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of May, 1981.



*Suzanne M. Hofer*  
Suzanne M. Hofer, Notary Public