

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-195-20875-00-00

API NUMBER 15-195-20,875-00-00

LEASE NAME Comeau

WELL NUMBER 1

SPOT LOCATION C SE NW

SEC. 6 TWP. 11S RGE. 23W (E) or (W)

COUNTY Trego

Date Well Completed 11-25-81

Plugging Commenced 11/20/85

Plugging Completed 1/8/86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F & M OIL CO., INC.

ADDRESS 422 Union Center, Wichita, Kansas 67202

PHONE # (316) 262-2636 OPERATORS LICENSE NO. 5313

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? -----

Producing formation Lansing Depth to top 3656' bottom 3893' T.D. 3939'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	213'	None
				4 1/2"	3937'	2494'
Lansing	Oil & Water	3656'	3893'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3600' & 4 sacks cement. Shot pipe at 2930', 2707', and 2494'. Pulled 62 joints of pipe. Plugged well with 3 hulls, 25 gel, 100 cement with hulls, 15 gel, 8 5/8 plug, & 80 sacks 60/40 poz 6% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1986

My Commission expires: _____



Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
1-13-1986
JAN 13 1986

CONSERVATION DIVISION
Wichita, Kansas