

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: C & K Oil

Address: P.O. Box 531 Clafin, Kansas 67525

Phone: (620) 786-8744 Operator License #: 31561

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Bruce Rodio (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-20815-00-00

Lease Name: Kimpler "B"

Well Number: 2

Spot Location (QQQQ): _____ - N/2 - SE - NE
1680 Feet from North / South Section Line
660 Feet from East / West Section Line

Sec. 31 Twp. 18 S. R. 11 East West

County: Barton

Date Well Completed: _____

Plugging Commenced: 3-2-09

Plugging Completed: 3-3-09

KCC
PKT
PEP
OPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	245'	None
				4-1/2"	3413'	400'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3300' and 4 sxs. cement. Casing parted @400', layed down casing, ran 2-3/8" tubing to 1050', perforated casing @1060', pumped 70 sxs. cement @1050', puiled up to 675', pumped 35 sxs. cement w/150# hulls, pulled up to 350, pumped 130 sxs. cement w/100# hulls, layed rest of casing down. Used 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: C & K Oil

State of Kansas County, Rice, ss.


KANSAS CORPORATION COMMISSION
MAR 19 2009
RECEIVED

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 18th day of March, 20 09

Irene Herzberg Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT