

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: L.D. Hale
Address: 15000 Timber Lake Road Wichita, Kansas 67230
Phone: (316) 838-0093 Operator License #: 3910
Type of Well: Oil DH KCCP/KC Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-22,253-0000
Lease Name: Wells
Well Number: 2-35
Spot Location (QQQQ): _____ - N 2 - NE - NE
330 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 35 Twp. 27 S. R. 11 East West
County: Pratt
Date Well Completed: _____
Plugging Commenced: 2-27-09
Plugging Completed: 3-2-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				7"	280'	None
				4-1/2"	1682'	1320'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 1500' and 4 sxs. cement. Cut casing loose @1320'. pulled up to 600', pumped 10 sxs. gel and 40 sxs. cement. pulled up to 300'. pumped 40 sxs. cement, pulled up to 40' and circulated 20 sxs. cement to surface. 60/40 pos, 4% gel.
Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: L.D. Hale
State of Kansas County, Rice, ss.

KANSAS CORPORATION COMMISSION
MAR 19 2009
RECEIVED


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 18th day of March, 2009

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PWT