


•Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 10 Twp. 11S Rge. 23W (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW NE NE
Lease Owner Martin & Keller
Lease Name Heckman Well No. 2 1-A
Office Address 1035 Kennedy Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-6-65 19
Application for plugging filed 11-6-65 19
Application for plugging approved 11-6-65 19
Plugging commenced 11-6-65 19
Plugging completed 11-6-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Ks.
Producing formation Depth to top Bottom Total Depth of Well 3743' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Plug @ 540' with 20 sacks cement
Set Plug @ 200' with 20 sacks cement
Bridged plug @ 40' with 1/2 sk. hulls, 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
11-12-1965
NOV 12 1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas 67530

STATE OF ~~KAN~~ KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 65

My commission expires April 1, 1967 Notary Public.

15-195-30102-00-00

DRILLER'S LOG

COMPANY: Martin & Keller
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: HECKMAN #2
 LOCATION: NW NE NE Sec. 10-11S-23W
 TREGO COUNTY, KANSAS
 COMMENCED: 10-29-65
 COMPLETED: 11-6-65

0	205	Subsoil, shale, sand
205	880	Shale
880	1580	Sand, shale
1580	1732	Shale, redbed
1732	1775	Anhydrite
1775	1880	Shale, shells
1880	2250	Shale
2250	2440	Shale, lime
2440	3110	Lime, shale
3110	3330	Shale, lime
3330	3743	Lime
	<u>3743</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION
 11-12-1965
 NOV 12 1965
 CONSERVATION
 WICHITA, KANSAS

Set 8 5/8" used surface casing @ 205' with 175 sacks 60-40 Posmix
 Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Heckman #2 well, located
 NW NE NE of Section 10, Township 11 South, Range 23 West, Trego
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in
 and for Barton County, Kansas, this 10th day of November, 1965.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967