

15-195-00233-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Trego County, Sec. 10 Twp. 11 Rge. 23 (W)

Location as "NE/CNW/SW" or footage from lines SW NE SW
Lease Owner Icer Addis
Lease Name Galloway Well No. 1
Office Address Box 27 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed August 12 19 58
Application for plugging filed August 12 19 58
Application for plugging approved 19
Plugging commenced 8:00 a.m. August 12 19 58
Plugging completed 10:30 a.m. " " 19 58
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fabaius
Producing formation none Depth to top Bottom Total Depth of Well 3750' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 600' with 25 sx cement, Second plug at 215' with 1/2sx hulls and 15 sx cement, third plug at 40' with 1/2 sack of hulls and 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle drilling, Inc.
Address Box 287 Russell, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Donald D. Vaughan (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan
1211 Coofidge Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 58

My commission expires April 29, 1961 Dean E. Cooley Notary Public.

PLUGGING
FILE SEC 10 T. 11 R. 23W
BOOK PAGE 124 LINE 10

8-20-1958

WELL LOG

COMPANY Icer Addis
 CONTRACTOR Triangle Drilling, Inc.
 FARM #1 Galloway
 LOCATION SW NE SW of Section 10-11-23W
 Trego County, Kansas
 ELEVATION 2265 KB
 SURFACE PIPE 8 5/8" cemented at 217' w/175 sacks
 PRODUCTION D & A
 COMMENCED August 2, 1958
 COMPLETED August 12, 1958

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay	10
Sandstone	70
Shale and limestone	100
Shale, clay and sandstone streaks	200
Blue shale and clay	217
Shale and shells	760
Sandstone	875
Shale and sandstone	995
Sandstone	1060
Shale and red bed	1195
Sandstone	1420
Sandstone & shale	1480
Red bed	1734
Anhydrite	1775
Shale, shells & sandstone	1910
Shale and shells	2310
Sandy limestone and shale	2410
Limestone and shale	3244
Limestone	3738
Shale	3750

FORMATION TOPS

Anhydrite	1734 (/ 531) driller's
Topeka	3244 (- 979)
Heebner	3478 (-1213)
Toronto	3498 (-1233)
Lansing	3513 (-1248)
Base Kansas City	3738 (-1473)
RTD	3750 (-1485)

PLUGGING
 FILE SEC 10 T 11 R 23W
 BOOK PAGE 124 LOT 10

A F F I D A V I T

STATE OF KANSAS, COUNTY OF Barton, SS

I, Donald D. Vaughan, of the TRIANGLE DRILLING, INC., being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
 Donald D. Vaughan

Subscribed and sworn to before me this 18 day of August, 1958.

8-20-1958
 NOTARY PUBLIC DIVISION
 Kansas

Dean E. Cooley
 Notary Public Dean E. Cooley

My commission expires: April 29, 1961