

15-195-21983-00-00

LEASE NAME Denison

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 4

2,310 Ft. from S Section Line

1,650 Ft. from E Section Line

LEASE OPERATOR Shields Oil Producers, Inc.

SEC. 10 TWP. 11 RGE. 23 (E) or (W)

ADDRESS Shields Bldg., Russell, Kansas

COUNTY Trego

PHONE# (913) 483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed 8-18-88

Character of Well D & A

Plugging Commenced 8-18-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-18-88

The plugging proposal was approved on 8-19-88 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,758'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	217'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Push bridge plug to 1,780', pump 25 sax cement down 4 1/2" drill pipe. Push bridge plug to 920', pump 100 sax cement down 4 1/2" drill pipe. Push bridge plug to 230', pump 40 sax cement down 4 1/2" drill pipe. Push bridge plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or (~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Inc - Pres.

(Address) Shields Bldg., Russell, Ks. 67665

RECEIVED
 STATE CORPORATION COMMISSION
 9-8-1988
 SEP - 8 1988

SUBSCRIBED AND SWORN TO before me this 6th day of September, 19 88

Ruth Phillips
 Notary Public

CONSERVATION DIVISION
 State of Kansas
 Commission Expires: _____

