

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-195-21937-00-00

API NUMBER 15-195-21,937-00-00

LEASE NAME McCall

WELL NUMBER 1

4,290 Ft. from S Section Line

3,630 Ft. from E Section Line

SEC. 10 TWP. 11 RGE. 23 (E) or (W)

COUNTY Trego

Date Well Completed 11-23-87

Plugging Commenced 11-23-87

Plugging Completed 11-24-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS P.O. Box 709, Russell, Kansas 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5,184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,769'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	301'	Cmtd. w/170 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Fill hole w/heavy mud. Push bridge plug to 1,800', spot 25 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 935', spot 100 sax cement on plug. Push bridge plug to 330', spot 40 sax cement on plug. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address P.O. Box 709, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Russell, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec.-Treas.

(Address) P.O. Box 709, Russell, Kansas

SUBSCRIBED AND SWORN TO before me this 9th day of December 19 87

Ruth Phillips  
Notary Public

My Commission Expires:



RECEIVED  
STATE CORPORATION COMMISSION  
12-11-1987  
Wichita, Kansas  
Form CP-4  
Revised 08-84