

15-195-19035-00-00

10

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Trego County, Sec 11 Twp. 11S Rge. 23W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Martin & Keller

Lease Name Heckman Well No. 1

Office Address 1035 Kennedy Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil ~~XXXXXXXX~~

Date well completed 7-25-64 19

Application for plugging filed 8-25-66 19

Application for plugging approved 8-28-66 19


Plugging commenced 9-6-66 19

Plugging completed 9-8-66 19

Reason for abandonment of well or producing formation Depletion of producing formation

If a producing well is abandoned, date of last production May 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas

Producing formation Lansing-Kansas City Depth to top 3474 Bottom 3698' Total Depth of Well 3732 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	Oil	3678'	3696'	4 1/2"	3731'	180'
				8 5/8"	207'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed wood plug with bailer or wire line to 3640'; dumped 10' of sand down casing on top of plug. Using dump bailer, dumped 3 sacks of cement on top of sand. ~~XXXXXXXXXXXXXXXXXXXX~~ Pushed wood plug to 530'; dumped 15' of sand on top of plug; backed out and pulled 6 joints 4 1/2" casing; dumped 6 yards of ready-mix concrete down 8 5/8" surface pipe.

9-13-1966
SEP 13 1966
STATE CORPORATION COMMISSION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Herman Barnett (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herman Barnett

Box 486, Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN to before me this 10th day of September, 19 66

My commission expires April 1, 1967

Ulanda Nichols
Ulanda Nichols
Notary Public.

15-195-19035-00-00

DRILLER'S LOG

COMPANY: Martin & Keller
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: HECKMAN #1
 LOCATION: 50' SE of NW NW SW
 TREGO COUNTY, KANSAS
 COMMENCED: 7-9-64
 COMPLETED: 7-17-64

0	150	Shale & Sand
150	1400	Shale & Shells
1400	1454	Shale & Sand
1454	1687	Red Rock & Sand
1687	1729	Anhydrite
1729	2080	Shale & Shells
2080	2345	Shale & Lime
2345	2660	Lime & Shale
2660	3255	Shale & Lime
3255	3732	Lime
	<u>3732</u>	<u>Rotary Total Depth - Set 4 1/2"</u>

RECEIVED
 STATE CORPORATION COMMISSION
 8-26-1966
 AUG 16 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Casing

Set 8 5/8" casing @ 207' with 175 sacks Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Heckman #1 well, located 50' Southeast of NW NW SW of Section 11, Township 11 South, Range 23 West, Trego County, Kansas, this as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 20th day of July, 1964.

Ulanda Nichols

 Ulanda Nichols

My Commission Expires:
April 1, 1967