

15-051-20668-00-00

KANSAS

Form CP-3
Rev. 6-4-68

Jo
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
10-5-1970
OCT 5 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Et al

Complete Address 200 W. Douglas Wichita, Kansas

Lease Name Metz Well No. 1

Location NW NE NW Sec. 24 Twp. 11 Rge. (E) (W)19

County Ellis Total Depth 3488

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 5:30 A Day 2 Month 10 Year 1970

The above well was plugged as follows:

RTD 3488' 8 5/8 csg set at 205' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo L. Messer
Well Plugging Supervisor

DATE 10-5-70

INV. NO. 2620-W