

15-051-05881-00-00

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 1-29 Location: NW SW SW
County: Ellis Sec. 24 Twp. 11 Rge. 19 (E) (W)
Name of Field or Pool: _____ Total Depth: 5000

I have this date completed supervision of plugging of:

Well No. 2 Lease Richards
Operator's Full Name John O. Farmer
Complete Address: Russell, Kans
Plugging Contractor: West Supply Co
Address: Chase, Kans License No. 14
Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____
If well is a rotary drilled dry hole did operators wait for you to arrive _____
If yes how long _____ Reason: _____

Operation Completed: Hour _____ oPM Day 10 Month 12 Year 58

The above well was plugged as follows:

8 5/8" at 100' circulated with cement - 5 1/2" 5000' with 50 sax cement.
Filled with sand to 5590', set 4 sax cement with dump bailer, pulled
5000' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (20 sax
Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 100',
displaced 20 sax cement through 5 1/2" at 100', heavy mud to 55', set
rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's Pump truck.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Edon Lesty*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
12-24-1958
DEC 24 1958

CONSERVATION DIVISION
Wichita, Kansas

Reviewed: *J. Lewis Bush*
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks: _____

PLUGGING
FILE SEC. 24 T. 11 R. 19W
BOOK PAGE 1 LINE 29