

15-051-23080-00-0-0

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-23,080

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name DON E PEATTY OIL OPERATIONS

Complete Address 1011 FORT. HAYS, HAYS, 67601

Lease Name SOLOMON Well No. "C" - 129

Location NW-NW-SW Sec. 29 Twp. 11 Rge. 19 (East)(West)

County ELLIS Total Depth 3719 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor MURFIN DRILLING (Rig 16) (EDWARD SCHOOL)

Address 617 UNION CENTER, WICHITA, KS. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 4:15 PM Day: 1 <sup>ST</sup> Month: AUG. Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 189 FE 50. CUC. ~ / 145 ST COMMON QUICK SET. (BY ALLIED)

ORDERED 140 ST 50/50 PORMIX 4% GEL - 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1 ST PLUG. @ 870 FE ~ / 80 ST CMT.

2 ND PLUG. @ 270 FE ~ / 40 ST CMT.

3 RD PLUG. -> SOLID BRIDGE MUD'S - PLUG. @ 40 FE / 0 ~ / 10 ST CMT.

10 ST IN RAT HOLE (CIRCULATE)

CEMENTED BY ALLIED CMT.

Amount of Surface Casing: 189 FE

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Merrill J. Schmidt  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 8-19-82

INV. NO. 939-W

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 09 1982  
CONSERVATION DIVISION  
Wichita, Kansas

